



**EXCENTIS**

Excellence in Network Technologies  
and Telecommunications

**WSP**

**WSP/AS Validation Test Service ATP**

**Global Network Vendor Certification**

x/y/z Project reference:SO/xxx/yyyy

Revision: 01

Distribution: Provided under NDA by Excentis to **WSP,**

**EXCENTIS**

Gildestraat 8  
9000 Gent  
Belgium

T +32 9 269 22 91  
E info@excentis.com  
www.excentis.com

1177 Ave of the Americas  
New York, NY 10036  
United States

T +1 347 720 6896  
E info@excentis.com  
www.excentis.com



**WSP can share this report with WSP**

## **EXCENTIS**

Gildestraat 8  
9000 Gent  
Belgium

1177 Ave of the Americas  
New York, NY 10036  
United States

T +32 9 269 22 91  
E [info@excentis.com](mailto:info@excentis.com)  
[www.excentis.com](http://www.excentis.com)

T +1 347 720 6896  
E [info@excentis.com](mailto:info@excentis.com)  
[www.excentis.com](http://www.excentis.com)



## TABLE OF CONTENTS

<b>1. Executive summary .....</b>	<b>4</b>
<b>2. Test Results .....</b>	<b>6</b>
2.1 BsoD Service Fairness.....	9
2.2 BSoD .....	10
2.3 Config and SNMP Software Upgrade D3.1 .....	10
2.4 Device Reset.....	13
2.5 Device Reset 3.1 .....	13
2.6 Downstream Partial Service .....	14
2.7 Features.....	14
2.8 Filtering.....	15
2.9 FTP Application.....	15
2.10 Loadbalancing .....	17
2.11 MTA Disable .....	17
2.12 Network Access Disabled.....	19
2.13 Rate Limiting.....	19
2.14 SNMP Management.....	22
2.15 Stability Test.....	24
2.16 Node Split and Transients.....	24
2.17 Timers and Events.....	25
2.18 Upstream Partial Service.....	25
2.19 Version Capabilities .....	27
2.20 Second syslog .....	27
2.21 D3.1 Features.....	28
<b>3. CM Configfile .....</b>	<b>29</b>
<b>4. Revision History.....</b>	<b>30</b>





## 2. Test Results

Tests are executed on a [REDACTED]

WHO DUT sysDescr:

[REDACTED]

An overview of the test results:

Test	PASS/FAIL	Observation
BsoD Service Fairness	[REDACTED]	[REDACTED]
BsoD	[REDACTED]	[REDACTED]
Config and SNMP Software Upgrade	[REDACTED]	[REDACTED]
Device Reset	[REDACTED]	[REDACTED]
Device Reset 3.1	[REDACTED]	[REDACTED]
Downstream Partial Service	[REDACTED]	[REDACTED]
Features	[REDACTED]	[REDACTED]
Filtering	[REDACTED]	[REDACTED]
FTP Application	[REDACTED]	[REDACTED]
Loadbalancing	[REDACTED]	[REDACTED]
MTA Disable	[REDACTED]	[REDACTED]
Network Access Disabled	[REDACTED]	[REDACTED]
Rate Limiting	[REDACTED]	[REDACTED]
SNMP Management	[REDACTED]	[REDACTED]

Stability Test	XXXXXXXXXX	XXXXXXXXXX
Node Split and Transients	XXXXXXXXXX	XXXXXXXXXX
Timers and Events	XXXXXXXXXX	XXXXXXXXXXXXXXXXXXXXXXXXXXXX
Upstream Partial Service	XXXXXXXXXX	XXXXXXXXXX
Version Capabilities	XXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
Second syslog	XXXXXXXXXX	XXXXXXXXXXXXXXXXXXXX
D3.1 features	XXXXXXXXXX	XXXXXXXXXX

### Fail and remark descriptions

#### eRouter not using NAT

The eRouter does not apply the NAT rule to packets coming from the VPN clients. This is because the router is not configured to do so.

#### LAN DHCP issues

The eRouter does not respond to DHCP requests from LAN clients. This is because the router is not configured to do so.

#### ARP within L2VPN fails

The eRouter does not respond to ARP requests from LAN clients. This is because the router is not configured to do so.

The eRouter does not respond to ARP requests from LAN clients. This is because the router is not configured to do so.



## 2.1 BsoD Service Fairness

### Introduction

This regression test verifies service fairness. If internet service is provided via Alternative Operator configuration, the maximum speeds offered through this service is compared with normal Operator based internet services. The obtained maximum service throughput for both deployments is expected to be equal.

This fairness check is done under congested and non congested conditions.

### Observations

The throughput results are very similar for the Alternative and the Normal Operator, both in congested and non-congested conditions.

To compare between non-L2VPN [REDACTED] and VPN condition [REDACTED] the time was measured for downloads (1.6 GB size = DS).

Test case	Non-L2VPN duration	L2VPN duration	Result
TestCase 1 DS (Non-Congested)	[REDACTED]	[REDACTED]	[REDACTED]
TestCase 2 DS (Congested)	[REDACTED]	[REDACTED]	[REDACTED]

### Result

[REDACTED]

## 2.2 BSoD

### Introduction

The objective of this test is to verify that the CM supports the BSoD-related requirements for implementing services on the Business Overlay CMTS network. It is checked if it correctly behaves in a BSoD environment by testing:

- BSoD configuration
- BSoD activation
- BSoD support
- BSoD recovery
- BSoD configuration and BSoD management commands to the CM

### Observations

The BSoD configuration is correct. The BSoD activation is successful. The BSoD support is correct. The BSoD recovery is successful. The BSoD configuration and BSoD management commands to the CM are correct.

### Result

Pass

## 2.3 Config and SNMP Software Upgrade D3.1

### Introduction

This test confirms that the CM will upgrade or downgrade to a specific software in different situations using SNMP or CM configuration file. The correct CM events, syslogs,... should be shown if upgrade or downgrade fails. The different situations (subtests) are:

1. Upgrade using SNMP
2. Downgrade using SNMP

- 1. [Redacted]
- 4. [Redacted]
- 2. [Redacted]
- 6. [Redacted]
- 7. [Redacted]
- 3. [Redacted]
- 5. [Redacted]

WHO will only upgrade the modems using D3.1 signed images (using 3.1 CVC chain).

**Observations**

Since the D3.1 software file size is about 75 MB (including RDK-B stack), HTTP download is recommended.

**Following subtests had a remark:**

**Subtest 1**

[Redacted]

[Redacted]

**Subtest 2**

[Redacted]

[Redacted]

**Subtest 3**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

## Result

**[REDACTED]**

## 2.4 Device Reset

### Introduction

This test verifies that the CM resets & recovers in a timely manner (~ 2 minutes) when reset by SNMP and from the CMTS MAC Domain in D3.0 mode.

### Observations

[REDACTED]

### Result

[REDACTED]

## 2.5 Device Reset 3.1

### Introduction

This test verifies that the CM resets & recovers in a timely manner (~ 2 minutes) when reset by SNMP and from the CMTS MAC Domain in mixed D3.0/D3.1 mode.

### Observations

[REDACTED]

### Result

[REDACTED]

## 2.6 Downstream Partial Service

### Introduction

It is checked if the CM behaves correctly in partial service. RF channels will be disturbed so that it is no longer usable by the CM (e.g. by putting another downstream channel of a different MAC Domain or different CMTS on the same frequency on the same HFC network or by injecting a signal using a signal generator on the same downstream frequency) and restored to normal operation again.

It is also checked that the CM correctly reports the disconnected/reconnected channels via CM-STATUS messages. It is checked that the CM correctly reports partial service via REG-ACK messages.

If the disturbed channel is the primary downstream channel of the CM, the CM must not send CM-STATUS messages, but must reboot immediately.

Furthermore it is verified that in the case of partial service also traffic is forwarded as expected.

### Observations

**Regulation is observed.**

### Result

**Pass**

## 2.7 Features

### Introduction

The first subtest verifies that a user can't change modem specific settings from the internal website. A second subtest checks that a modem can register when the configuration file name contains special characters.

### Observations

**Regulation is observed.**

### Result

**Pass**

## 2.8 Filtering

### Introduction

Positive CM registration is tested using a non-existing OID in the CM configuration file as well as negative registration when using a CM configuration file with invalid formatted TLV11 entry or a duplicate TLV11 entry. Furthermore, a port scan is executed to check for unexpected open ports.

### Observations

The CM successfully registers when using a non-existing OID (example: 1.2.3.4.5.6.7.8.9) inside the CM configuration file, which is not allowed according to the standard. The CM successfully registers when a duplicate OID is inside the CM configuration file, also this is not allowed. However, according to the VMS VMS-ATP definition document it is required with VMS to adapt the ATP such that it does not cause the CM to be rejected. This for the reason that the VMS builder cannot be stopped in front of the customer using the registration from VMS to ensure that the CM is not rejected. Both tests should still however be added to the existing tests in the configuration file.

For both tests the device should be in a normal state.

When a port scan is performed, it was expected to see only ports 80 and 443 open, but the device also opens ports 22 and 23 which is not expected.

### Result

FAIL (partially)

## 2.9 FTP Application

### Introduction

This test verifies the interface between the FTP Server and the Residential Gateway products, i.e. the correct use of all OID's applicable for the FTP application features. The functionality is tested on downstream and upstream separately by means of configuration and functionality. Performance is tested individually on downstream and upstream but also using simultaneous sessions.

### Observations

**[REDACTED]**

**Result**

**[REDACTED]**



## 2.10 Loadbalancing

### Introduction

This test checks if the CM behaves correctly when load balancing (by using DCC and DBC messages) is enforced by the CMTS.

### Observations

[REDACTED]

[REDACTED]

[REDACTED]

- [REDACTED]
- [REDACTED]
- [REDACTED]
- [REDACTED]

### Result

[REDACTED]

## 2.11 MTA Disable

### Introduction

This test verifies how an embedded MTA in the Device Under Test can be disabled. Two disable methods are tested. The first method is disable via SNMP which sets the eMTA interface (ifIndex 16, PacketCable Embedded Interface) down which as such prohibits the eMTA from communicating. The second method uses the option 122 which will disable the eMTA component.

### Observations

This test is not applicable as the modem has no MTA.

### Result

NA



## 2.12 Network Access Disabled

### Introduction

This test verifies that if internet service on the CM is disabled (using NACO), the device is still manageable via SNMP from the operator side.

### Observations

**[REDACTED]**

### Result

**[REDACTED]**

## 2.13 Rate Limiting

### Introduction

This test verifies that maximum speeds as defined by CM configuration file can be obtained by the system. Rate limiting is happening as during production configuration. The maximum possible download and upload speed (UDP and TCP) is also measured for the CM tested and when available compared with the test results of previous software versions of the tested CM.

### Observations

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**

**[REDACTED]**



Throughput measurements with **unlimited** rate (using multiple flows):

**Mixed mode** (config 32DS x 4US + 1 OFDM x 1 OFDMA)

Flow	Down (Mbps)	Up (Mbps)
<i>UDP 256B</i>	886	198
<i>TCP</i>	1680	191
<i>Theoretical (Mbps)</i>	1770	203

**DOCSIS 3.0 mode** (config 32DS x 4US)

Flow	Down (Mbps)	Up (Mbps)
<i>UDP 256B</i>	857	94
<i>TCP</i>	1515	89
<i>Theoretical (Mbps)</i>	1580	98

**DOCSIS 3.1 mode** (1 OFDM x 1 OFDMA)

Flow	Down (Mbps)	Up (Mbps)
<i>UDP 256B</i>	172	103
<i>TCP</i>	170	105
<i>Theoretical (Mbps)</i>	189	105

## Result



## 2.14 SNMP Management

### Introduction

This test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. SNMP read/write access to the predefined MIB views using its SNMPv2c community strings are tested from the alternative operator's backbone, the operator's backbone and from CPE side.

### Observations

The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

- The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.
- The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.
  - The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.
  - The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.
  - The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined. The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

- The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.
- The test checks if the CM behaves correctly when SNMP access rules for the alternative operator are defined.

- [Redacted]

**Result**

[Redacted]

## 2.15 Stability Test

### Introduction

The objective of this test is to verify the stability/interoperability of a 3.0 CM in a simulated real-life setup (background noise disturbances, voice, UDP traffic and TCP sessions). It is expected that the 3.0 CM behaves correctly (based on packet loss and SNMP monitoring of the modems) over a period of 24h.

### Observations

[REDACTED]

### Result

[REDACTED]

## 2.16 Node Split and Transients

### Introduction

This test verifies proper behavior of the CM during a typical node split scenario. During a node split scenario, the CM is going to lose its RF connectivity (without reception of prior managed reboot commands) and will obtain new channels. This new set of channels, on the same frequencies, typically belongs to a different MAC Domain with its own configuration MAC Domain specific settings. During this switch the CM is expected to obtain a different IP address and other operational parameters. This test will verify this proper transition.

Subtest 2 was executed.

### Observations

[REDACTED]

### Result

[REDACTED]



## 2.17 Timers and Events

### Introduction

The objective of this test is to verify how CM timers will react & which events will be shown in different (network) situations.

CM resets or interruptions are tested triggered by:

- **CMR**
- **Poweroff**
- **Reset**
- **Short-Circuit**
- **Long-Circuit**
- **Short-Circuit**

### Observations

**The CMR, Poweroff, Reset, Short-Circuit, Long-Circuit, Short-Circuit events are triggered and the CM STATUS is updated accordingly.**

### Result

**Pass**

## 2.18 Upstream Partial Service

### Introduction

This test checks if it correctly behaves in upstream partial service and remains interoperable with the CMTS. Partial service is tested during normal operation with and without CM-STATUS messaging and during registration.

### Observations

**The CM STATUS is updated accordingly.**

### Result

**Pass**



## 2.19 Version Capabilities

### Introduction

In this test the objective is to check if the docsDevSwCurrentVers and docsIfDocsisBaseCapability MIB's and the DHCP parameters and options are filled in correctly. Furthermore the NACO capability is checked together with the LED indication.

### Observations

The system is running on the version of the software

version: 1.0.0 (running on the version of the software)

The system is running on the version of the software

version

The system is running on the version of the software of the version of the software

The system is running on the version of the software of the version of the software

- The system is running on the version of the software of the version of the software
- The system is running on the version of the software of the version of the software

### Result

The system is running on the version of the software of the version of the software

## 2.20 Second syslog

The system is running on the version of the software of the version of the software of the version of the software

### Result

The system is running on the version of the software of the version of the software

## 2.21 D3.1 Features

### Introduction

This test plan covers the operational readiness of DOCSIS 3.1 CPE devices to interoperate on WHP's network. This ATP is written to verify if the CPE is ready for the WHP DOCSIS 3.1 network/topology. This test set is intended to be run each time when a new major software release of the modem vendor is to be introduced in the field.

### Observations

**Confidentiality: This document contains information that is confidential to the company and its customers. It is not to be distributed outside the company without the express written consent of the company. If you are not an intended recipient, you should not disseminate, distribute or take any action in reliance on the contents of this information. If you have received this document in error, please notify the sender immediately by e-mail. This document is confidential and intended only for the individual named. If you are not the named addressee you should not disseminate, distribute or take any action in reliance on the contents of this information.**

**For internal use only.**

### Result

**Pass**

### 3. CM Configfile

**[REDACTED]**

## 4. Revision History

Version 1.0: initial release